



REQUEST FORM FOR FILE WRAPPER CONTINUING APPLICATION
UNDER 37 CFR 1.62

Docket No. 35.C6297 Cont.

Anticipated Classification of
 this application:

Class _____ Subclass _____

Prior Application:

Examiner M. Shehata

Group Art Unit 2601

Commissioner of Patents
 and Trademarks
 Box FWC
 Washington, D.C. 20231

Sir:

This is a request for filing a continuation-in-part
 continuation divisional application, under 37 CFR 1.62 of
 prior application Serial No. 07/388,079 filed on August 1, 1989,
 currently entitled INFORMATION PROCESSING APPARATUS

by the following currently named inventors:

Full Name of Sole or First Inventor RYOICHIRO SATO
 Residence 10-3-315, Tsurumichuo 2-chome, Tsurumi-ku,
Yokohama-shi, Kanagawa-ken, Japan
 Citizenship Japan
 Post Office Address c/o CANON KABUSHIKI KAISHA
30-2, 3-chome, Shimomaruko, Ohta-ku, Tokyo, Japan

Full Name of Second Joint Inventor, if any YOJI FURUYA
 Residence 2-207, Ribere Koyodai, 5-10, Koyodai,
Inagi-shi, Tokyo, Japan
 Citizenship Japan
 Post Office Address c/o CANON KABUSHIKI KAISHA
30-2, 3-chome, Shimomaruko, Ohta-ku, Tokyo, Japan

Full Name of Third Joint Inventor, if any _____
 Residence _____ Citizenship _____
 Post Office Address _____

Full Name of Fourth Joint Inventor, if any _____
 Residence _____ Citizenship _____
 Post Office Address _____

Full Name of Fifth Joint Inventor, if any _____
 Residence _____ Citizenship _____
 Post Office Address _____

The above identified prior application in which no payment of the issue fee, abandonment of, or termination of proceedings has occurred, is hereby expressly abandoned as of the filing date of this new application. Please use all the contents of the prior application file wrapper, including the drawings, as the basic papers for the new application. (Note: 37 CFR 1.60 may be used for applications where the prior application is not to be abandoned.)

1. Enter the amendment previously filed on January 4, 1993 under 37 CFR 1.116 but unentered, in the prior application.
- 2a. A preliminary amendment is enclosed.
- 2b. The applicant(s) presently intend(s) to file additional papers in this case after receiving an official Filing Receipt. Should the Examiner take this case up for action before receiving such papers, it is respectfully requested that the Examiner contact the attorneys for the applicant(s) at the telephone number shown below.
- 3a. The filing fee is calculated below on the basis of the claims existing in the prior application as amended at 1 and 2 above:

EXISTING CLAIMS				
FOR	NUMBER FILED	NUMBER EXTRA	RATE	BASIC FEE
<u>TOTAL</u>			x \$11	\$355/\$710
<u>CLAIMS</u>	<u>14-20</u>	<u>0</u>	<u>\$22</u>	<u>\$ -0-</u>
<u>INDEP.</u>			x \$37	
<u>CLAIMS</u>	<u>3-3</u>	<u>0</u>	<u>\$74</u>	<u>\$ -0-</u>
<u>Fee for Multiple Dependent claims \$115/\$230</u>				
			<u>TOTAL FILING FEE -----</u>	<u>\$710.00</u>

- 3b. Verified Statement claiming small entity status is enclosed or was filed in a prior application.
- 3c. Any prior general authorization to charge an issue fee under 37 C.F.R. 1.18 to Deposit Account No. 06-1205 is hereby revoked. The Commissioner is hereby authorized to charge any fees which may be required during the entire pendency of this application under 37 CFR 1.16 and 1.17, or to credit any overpayment, to Deposit Account No. 06-1205. A duplicate copy of this form is enclosed.

SEARCHED SERIALIZED INDEXED FILED

4a. A check in the amount of \$710.00 is enclosed.

4b. The filing fee will be supplied later.

5. Since this application is a continuation-in-part which discloses and claims additional matter, a new oath or declaration is included will be supplied later.

6. Amend the specification by inserting before the first line the sentence: --This application is a continuation-in-part continuation division, of application Serial No. 07/388,079 filed August 1, 1989.--.

7. Priority of the following applications are claimed under 35 U.S.C. 119:

<u>Country</u>	<u>Application No.</u>	<u>Filed (Mo., Day & Yr.)</u>
Japan	63-193299	August 2, 1988
Japan	63-223626	September 8, 1988
Japan	63-312926	December 13, 1988

8. The prior application is assigned of record to:

CANON KABUSHIKI KAISHA

9. The power of attorney in the prior application is to:

Joseph M. Fitzpatrick (Registration No. 17,398), Lawrence F. Scinto (Registration No. 18,973), William J. Brunet (Registration No. 20,452), Robert L. Baechtold (Registration No. 20,860), John A. O'Brien (Registration No. 24,367), John A. Krause (Registration No. 24,613), Henry J. Renk (Registration No. 25,499), Peter Saxon (Registration No. 24,947), Anthony M. Zupcic (Registration No. 27,276), Charles P. Baker (Registration No. 26,702), Stevan J. Bosses (Registration No. 22,291), Edward E. Vassallo (Registration No. 29,117), Ronald A. Clayton (Registration No. 26,718), Lawrence A. Stahl (Registration No. 30,110), Laura A. Bauer (Registration No. 29,767), Leonard P. Diana (Registration No. 29,296), David M. Quinlan (Registration No. 26,641), Nicholas N. Kallas (Registration No. 31,530), William M. Wannisky (Registration No. 28,373), Lawrence Alaburda (Registration No. 31,583), Lawrence S. Perry (Registration No. 31,865), Robert H. Fischer (Registration No. 30,051), Christopher Philip Wrist (Registration No. 32,078), Gary M. Jacobs

(Registration No. 28,861) and Michael K. O'Neill (Registration No. 32,622).

10. Recognize as Associate Attorneys:

Bruce C. Haas (Registration No. 32,734), Scott K. Reed (Registration No. 32,433), Scott D. Malpede (Registration No. 32,533), John A. Mitchell (Registration No. 19,032), Fredrick M. Zullow (Registration No. 32,452), Richard P. Bauer (Registration No. 31,588), Warren E. Olsen (Registration No. 27,290), Abigail F. Cousins (Registration No. 29,292), Jennifer A. Tegfeldt (Registration No. 31,310), Steven E. Warner (Registration No. 33,326), Thomas J. O'Connell (Registration No. 33,202), Aaron C. Deditch (Registration No. 33,865), Penina Wollman (Registration No. 30,816), David L. Schaeffer (Registration No. 32,716), Jack S. Cubert (Registration No. 24,245), Mark A. Williamson (Registration No. 33,628), John T. Whelan (Registration No. 32,448), Patricia M. Drost (Registration No. 29,790) Jean K. Dudek (Registration No. 30,938), Raymond R. Mandra (Registration No. 34,382), Dominick A. Conde (Registration No. 33,856), Steven C. Bauman (Registration No. 33,832), Pasquale A. Razzano (Registration No. 25,512), John W. Behringer (Registration No. 23,086), Robert C. Kline (Registration No. 17,739), Carolyn H. Blankenship (Registration No. 35,449), Richard F. Jaworski (Registration No. 33,515), Lawrence W. Nelson (Registration No. 34,684), Benjamin C. Hsing (Registration No. 34,528), Leo J. Jennings (Registration No. 32,902), Mark J. Itri (Registration No. 36,171) and William C. Hwang (Registration No. 36,169).

11. Also enclosed:

Petition Under 37 C.F.R. § 1.136(a) and check for \$110.00.

12. Applicants' undersigned attorney may be reached in our New York Office by telephone at (212) 758-2400 or by facsimile at (212) 758-2982. All correspondence should continue to be directed to our address listed below.

13. Address all future communications to:

Fitzpatrick, Cella, Harper & Scinto
277 Park Avenue
New York, N.Y. 10172

It is understood that secrecy under 35 U.S.C. 122 is hereby waived to the extent that if information or access is available to any one of the applications in the file wrapper of a

37 CFR 1.62 application, be it either this application or a prior application in the same file wrapper, the Patent and Trademark Office may provide similar information or access to all the other applications in the same file wrapper.

Dated: 2/4/93

Richard P. Bower
Attorney for Applicants
Reg. No. 31,588

FITZPATRICK, CELLA, HARPER & SCINTO
277 Park Avenue
New York, New York 10172

F511/A119976

RECORDED - FEB 10 1993



CFO 6297 US

1

5

10

S P E C I F I C A T I O N

15 TO ALL WHOM IT MAY CONCERN:

Be it known that we, RYOICHIRO SATO and
YOJI FURUYA, subjects of Japan, respectively at
10-3-315, Tsurumichuo 2-chome, Tsurumi-ku, Yokohama-shi,
Kanagawa-ken, Japan, 2-207, Ribere Koyodai, 5-10,

20 Koyodai, Inagi-shi, Tokyo, Japan, have jointly invented
a certain new and useful improvement in INFORMATION
PROCESSING APPARATUS, of which the following is a full,
clear, concise and exact description.

25



370.00 101-A

11/388079

- 1 -

1 TITLE OF THE INVENTION:

Information Processing Apparatus

INS
FI

BACKGROUND OF THE INVENTION:

(a) Field of the Invention

5 The present invention relates to an information processing apparatus and, more particularly, to an information processing apparatus having a telephone function or communication function and a character recognition function.

10 (b) Related Background Art

In recent years, a multi-functional information processing apparatus having, e.g., a personal computer function and a telephone function or facsimile function has been widely used. In order to input data such as a 15 "company name" and a "telephone number" described on a printed matter, e.g., a name card or pamphlet and to register the data as a data base, a keyboard and a display are used to input the data.

In the above conventional apparatus, however, 20 although an image scanner as a facsimile function can read a printed matter such as a card or pamphlet, data can be input by only a key input operation performed by an operator. Therefore, input errors and the like easily occur and an input time is prolonged to decrease 25 an operation efficiency.

In the above conventional information processing apparatus, customer information such as a "company

DEPARTMENT OF STATE
REGISTRATION AND EXAMINATION
OF TRADEMARKS

1 name" and a "telephone number" registered as a data
base are stored in units of indexes in the order of
kana syllabary (a, i, u, ..., o, n) or in the
alphabetical order. In order to use the above customer
5 information for the facsimile function or telephone
function, an index is designated, customer information
belonging to the designated index is displayed on a
display, and an item to be transmitted is designated
from the displayed customer information.

10 In the above conventional technique, however,
since each transmission customer is simply displayed on
the display in units of indexes and selected, a
transmission customer must be designated for each
index. Therefore, when a plurality of transmission
15 customers or transmission customers in different
indexes are to be designated, ^{the} ~~an~~ operation is
complicated. In particular, it is difficult to
simultaneously designate a plurality of transmission
customers in order to perform multi-address
20 transmission.

For this reason, since data for multi-address
transmission must be additionally registered, a data
processing function of a personal computer has not been
sufficiently achieved.

25 In the above information processing apparatus, an
index to which data of a required transmission customer
belongs must be known. If an index is not known,

1 indexes must be sequentially called and checked to
result in a very cumbersome operation. The data
processing function of a personal computer has not been
sufficiently achieved also in this point of view.

5 SUMMARY OF THE INVENTION:

10 The present invention has been made to solve the
above problems and has as its object to provide an
image processing apparatus capable of reading image
information and registering information obtained by
character recognition as a data base.

15 It is another object of the present invention to
provide an image processing apparatus capable of
utilizing transmission customer data registered in a
data base more effectively, thereby increasing an
operation efficiency in multi-address transmission or
the like.

20 It is still another object of the present
invention to provide an information processing
apparatus capable of reading image information
including telephone number data, performing character
recognition for the read image information and storing
the image information as a data base, and when the
telephone number data included in the image information
stored as the data base is searched, performing calling
in accordance with the searched telephone number data.

25 It is still another object of the present
invention to provide an information processing

DRAFTSHEET NUMBER

1 apparatus having a search function based on a key word
and capable of inputting a key word to select one or a
plurality of facsimile transmission customers from a
data base in which customer information of a plurality
5 of facsimile transmission customers are registered.

BRIEF DESCRIPTION OF THE DRAWINGS:

Fig. 1 is a block diagram showing an embodiment of the present invention;

Fig. 2 is a perspective view showing an outer appearance of the embodiment shown in Fig. 1;

Fig. 3 is a view showing a main menu;

Fig. 4 is a view showing a telephone menu;

Figs. 5 to 7 are views showing telephone book menus;

15 Figs. 8 to 10 are views showing card file menus;

Figs. 11A and 11B are views for explaining a method of inputting a character string in a card data frame;

Figs. 12 to 14 are views showing card file menus;

20 Fig. 15 is a flow chart for explaining operations
corresponding to respective icons;

Figs. 16A and 16B are flow charts for explaining operations of telephone book programs;

Figs. 17A to 17F are flow charts for
25 explaining operations of card file programs;

1 Fig. 18 is a view for explaining an analyzing
direction of each line on a card image in character
recognition;

5 Figs. 19A to 19D are flow charts for
explaining in detail parts of the procedures shown in
Figs. 17A to 17F;

Fig. 20 is a flow chart for explaining a
transmission operation in a facsimile function;

10 Fig. 21 is a view showing a relationship between
the contents of a telephone book file, a search key
word, and a FAX transmission list file;

Fig. 22 is a perspective view showing an outer
appearance of a telephone set as a most simple
application form of the present invention;

15 Fig. 23 is a block diagram of the telephone set
shown in Fig. 22;

Fig. 24 is a view for explaining a card conveyor
unit;

20 Figs. 25A to 25C are flow charts for
explaining operations of the telephone set shown in
Fig. 23;

Figs. 26A and 26B are views for explaining
card insertion directions;

25 Figs. 27A and 27B are views for explaining
search directions of image data;

Fig. 28 is a plan view of a telephone set as
another application form of the present invention;

1 Fig. 29 is a block diagram of the telephone set
shown in Fig. 28;

5 Figs. 30A and 30B are flow charts for
explaining operations of the telephone set shown in
Fig. 28;

10 Figs. 31A and 31B are flow charts for
explaining a part of the procedure shown in Fig. 30(a);
and

15 Fig. 32 is a view showing a matrix pattern on the
upper surface of the telephone set shown in Fig. 28.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS:

20 A preferred embodiment of the present invention
will be described below with reference to the
accompanying drawings.

25 <Description of Apparatus>

30 Fig. 1 is a block diagram showing an apparatus
according to the present invention. Referring to
Fig. 1, a central processing unit (to be referred to as
a CPU hereinafter) 1 controls the overall apparatus,
and a memory 2 includes control programs 2a, a display
icon font 2b, and a character font 2c. A touch panel 4
covers a display surface of a CRT display 3. When a
user activates an icon displayed on the CRT display 3,
an instruction is input to the apparatus. The CPU 1 is
connected to a keyboard 5 for key input, an auxiliary
storage 6 for storing the programs 2a or a large amount
of data (document data or the like to be transmitted by

SEARCHED - SERIALIZED - INDEXED - FILED

1 a facsimile function), a speaker 7 for alarming a user
of key input or occurrence of an error by a sound, an
image scanner 8 for reading a card image, a facsimile
9, a printer 10 for printing, and a telephone set 11
5 including a processing device (not shown) for a
telephone line and a handset 11a.

Fig. 2 is a perspective view showing an outer
appearance of the apparatus according to this
embodiment. Referring to Fig. 2, the touch panel 4
10 covers the CRT display 3 as described above. An
overall apparatus 12 includes a floppy disk insertion
port 13 constituting a part of the auxiliary storage 6,
a card inlet 14, a card outlet 15, a card guide 16, a
telephone line 17, and a power source 18.

15 Note that the ports 14 and 15 and the guide 16
have a size suitable for any sheet used in reading of
the facsimile, printing of the printer, or the like.

Fig. 3 shows a main menu displayed on the CRT
display 3 immediately after a power switch of the
20 apparatus 12 is turned on. When a user activates a
portion on the touch panel 4 located in front of the
screen by a finger 27, a program indicated by the
touched icon is activated. Referring to Fig. 3, an
icon 20 is for an "environment" program for adjusting a
25 speaker volume, screen brightness, and the like of the
apparatus 12, an icon 21 is for a "message" program for
leaving a message in the apparatus 12, an icon 22 is

CONFIDENTIAL

1 for a "telephone" program for setting a telephone menu,
an icon 23 is for a "fax" program for setting a fax
menu, an icon 24 is for a "wordprocessor" program, an
icon 25 is for a "card file" program for managing
5 cards, and an "end" icon 26 is for performing an end
operation. The auxiliary storage 6 stores a number of
various programs in addition to the above programs.
When a user aligns icons for programs to be activated
on the main menu screen, the programs can be
10 registered.

Fig. 4 shows the telephone menu displayed when the
"telephone" icon 22 on the main menu screen is
activated by a user. The telephone menu includes push
buttons 30, a display column 31 for displaying a number
15 input from the push buttons 30, an "environment"
program activating button 32 for setting a telephone
number, a music, and the like of the apparatus 12, a
hooking button 33, a tone switching button 34 for
sending tones of the push buttons to a customer, a
20 music start/end button 35, an off hook button 36 for
setting an off hook state without picking up the
handset, a telephone book button 37 for searching a
telephone number from "telephone book" data, a re-dial
button 38 for calling a customer of the same telephone
25 number if the customer is busy, a card file button 39
for searching a telephone number from "card file" data,

1 and an "end" button 26 for performing an end operation
of the telephone program.

Fig. 5 shows a telephone book menu displayed when
a user activates the telephone book button 37 shown in
5 Fig. 4. As shown in Fig. 5, the telephone book menu
includes an index 40 and a customer (name) 41. When a
user activates the customer 41, a phone call is
automatically made. The telephone book menu also
includes index buttons 42, a next page button 44 for
10 displaying a next page when a plurality of customer
data of the same index are present, and a preceding
page button 43 for displaying a preceding page. A
first page button 45 is for returning to a menu first
displayed when the telephone book button 37 is
15 activated.

Figs. 6 and 7 show menus displayed when a user
activates "Sa" and "Se" of the index buttons 42 shown
in Fig. 5, respectively.

Fig. 8 is a menu displayed when a user activates
20 the card file button 39 shown in Fig. 4 or the "card
file" icon 25 of the main menu shown in Fig. 3.

Referring to Fig. 8, the menu includes a frame 50
for displaying an image of a card read by the image
scanner 8, a frame 51 for displaying characters
25 obtained by analyzing the card image 50 by a pattern
matching method of character recognition, and a frame
52 for registering data of a card displayed in the

1 frame 51 as a data base in units of types. A section
53 indicates examples of items of card data, and a
section 54 indicates examples of raw data of a card.
These sections have columns of a company name 55, a
5 division 56, a title 57, a personal name 58, an address
59, a phone number 60, a fax number 61, and a memo 62.

The card data frame 52 is also used for data
search. Buttons 63 to 74 indicate function menus for
various processing tasks. A read button 63 is for
10 performing automatic processing tasks such as reading
of a card image into the image frame 50 performed by
the image scanner 8, character recognition,
determination of a type, and writing in the card data
frame 52. A register button 64 is for newly
15 registering data read in the card data frame 52 into a
"card file". An image button 65 is for newly
registering data similar to the register button 64 and
for additionally registering a card image. When a user
inputs characters in a part of the card data frame 52
20 and activates a search button 66, data coincident with
the characters is searched from the "card file", and a
search result is displayed in the card data frame 52 in
units of cases. A next page button 68 is for
displaying a next case, and a preceding page button 67
25 is for displaying a preceding case. A print button 69
is for printing all of searched data. A correct button
70 is for partially correcting a displayed case of data

SEARCHED INDEXED
SERIALIZED FILED

1 after searching and re-registering the data in the
"card file". A delete button 71 is for deleting a
displayed case of data after searching from the "card
file". A telephone book button 72 is for registering a
5 telephone number or fax number in the card data frame
52 into "telephone book" data. A call button 73 is for
performing automatic calling by a telephone number in
the card data frame 52. This internal operation is
similar to automatic calling using the telephone book
10 shown in Figs. 5, 6, and 7. A clear button 74 is for
clearing all of unnecessary data on the screen. A user
clears data by this button, inputs characters in a part
of card data, and activates the search button 66,
thereby searching data coincident with the input
15 characters from the "card file".

Fig. 9 shows a state in which a user sets a card
at the card inlet 14 from the state shown in Fig. 8
described above and activates the card read button 63
and card reading processing is completed. A card image
20 read from the image scanner 8 is displayed in the image
frame 50, character recognition is performed on the
basis of the image, and the recognition result is
displayed in the frame 51. Only card data whose types
are determined in the frame 51 are set in the card data
frame 52. Note that if the company name begins with
25 katakanas (hiraganas), the kana part is automatically
set in a column for data indicating how to read. A

DEPARTMENT OF DEFENSE

1 logo mark of the company name of the card image 50 is
not displayed in the character recognition result frame
51 because it is not recognized as a character.

5 Fig. 10 shows a state in which a user activates a
telephone character line "(03)-ooo-xxxx" in the
character recognition result frame 51 and immediately
activates the type frame of the phone number column 60
which is blank in Fig. 9 in the card data frame,
thereby automatically setting the telephone number in
10 the phone number column 60. Fig. 11A shows a state
in which a user causes a character cursor to appear in
the column of data indicating how to read which is
blank in Fig. 10 of the personal name column 58, and
Fig. 11B shows a state in which the user inputs data
15 indicating how to read from the keyboard 5. Fig. 12
shows a state in which the user activates a return key
after the operations shown in Figs. 11A and 11B,
thereby completing input of the data indicating how to
read in the personal name column 58.

20 Fig. 13 shows a state in which a user inputs
search characters "□□□□ Corporation" in the company
name column 55 immediately before activating the search
button 66. Note that the search characters can be
input by a method similar to that shown in Figs. 11A
25 and 11B, i.e., can be input by the cursor. Fig. 14
shows a state of a menu obtained by activating the
search button from the state shown in Fig. 13. A

DEPARTMENT OF DEFENSE

1 message 75 indicates that 11 cases of card data whose
company names coincide with the "□□□□Corporation" have
been found from the "card file" data. Data of the
first case is displayed from the company name column 55
5 to the memo column 62 in the card data frame 52. This
data is registered with an image, and a card image is
developed in the image frame 50. If a user wants to
see all of the 11 data, he or she need only repeatedly
activate the next page button 68 to sequentially
10 display the card data in the frame 52.

<Description of Operation>

Operations of the apparatus according to this
embodiment will be described below with reference to
flow charts shown in Figs. 15 to 17F.

15 Note that programs of this embodiment are started
when the apparatus 12 is connected to the power source
18, and the main menu shown in Fig. 3 is displayed on
the CRT display 3.

In step S1 shown in Fig. 15, whether a user
20 activates the "environment" icon is checked. If the
"environment" icon is activated, in step S2, the
environment menu is displayed to perform processing for
setting environments such as a speaker volume or screen
brightness by an input operation by the user. If the
25 end button 26 is activated, the flow advances to step
S13, and the screen is returned to the main menu. That
is, the flow returns to the start of this program.

1 Similarly, whether the other icons are activated
are checked in steps S3, S5, S7, S9, and S11. If any
icon is activated, a program corresponding to the
activated icon is activated to execute corresponding
5 processing in step S4, S6, S8, S10, or S12. For
example, if the "message" icon is activated, the
message menu is displayed in step S4 to execute
"message" processing for storing a message in the
apparatus 12. If the "telephone" icon is activated,
10 the "telephone" menu is displayed in step S6 to execute
a telephone operation by the user. If the "fax" icon
is activated, the "fax" menu is displayed in step S8 to
execute a fax operation by the user. If the
"wordprocessor" icon is activated, the wordprocessor
15 menu is displayed in step S10 to execute word
processing by the user. If the "card file" icon is
activated, the "card file" menu is displayed in step
S12 to execute card data addition and search by the
user.

20 The auxiliary storage 6 stores a number of various
programs in addition to the above programs. Therefore,
the user can align program icons on the main menu and
add them as programs which can be immediately
activated. In the flow chart of Fig. 15, programs are
25 similarly added after steps S11 and S12.

 The "wordprocessor" program in step S10 of Fig. 15
includes a function of directly facsimile-transmitting

1 a processed document in addition to a function of
printing it on paper as an output.

Figs. 16A and 16B are flow charts for
explaining programs corresponding to the "telephone
5 book" icon described with reference to Figs. 5 to 7.

In step S20, the "telephone book" menu is
displayed. In step S21, "A" is set as the index 40,
and customers 41 starting with "A" are displayed. At
the same time, "A, Ka, Sa, Ta, Na, Ha, Ma, Ya, Ra, and
10 Wa" is set in the index buttons 42. In step S22,
whether the user activates the customer 41 is checked.
If the customer 41 is activated, the flow advances to
step S23, and whether the handset 11a is off-hooked is
checked. If the handset 11a is off-hooked, the
15 telephone set 11 is instructed to make a call by using
a telephone number recorded in the customer 41 in step
S24, and the flow advances to step S25. If "NO"s are
determined in steps S22 and S23, the flow advances to
step S25, and whether the user activates the next page
20 button 44 is checked. If "YES" in step S25, the flow
advances to step S26, and whether a large number of
customers 41 are currently present and subsequent
customers 41 not displayed yet are present is checked.
If it is determined in step S27 that a next customer
25 group is present, the next customer group is displayed
in the customer 41 in step S28. After this display, if
"NO" is determined in step S25 or S27, the flow

1 advances to step S29, and whether the user activates
the preceding page button 43 is checked. If the
preceding page button 43 is activated, whether a large
number of customers 41 of the current index 40 are
5 present and previous customers 41 not displayed yet are
present is checked in step S30. If it is determined in
step S31 that a preceding customer group is present,
the preceding customer 41 group is displayed in step
S32. After this display, if "NO"s are displayed in
10 steps S29 and S31, the flow advances to step S33, and
whether the user activates the first page button 45 is
checked. If the first page button 45 is activated,
processing from step S21 is repeated. If the first
page button 45 is not activated, the flow advances to
15 step S34, and whether the user activates the index
button 42 is checked. If the index button 42 is
activated, a reading of the activated index button 42
is set in the index 40 and customers 41 starting with
the index 40 are displayed in step S35. In step S36,
20 the index buttons 42 are updated. That is, if the
index 40 is any of "A, K, S, T, N, H, M, Y, R, and W",
five characters associated with the activated index are
set in the index buttons 42. For example, if "S" is
the index 40, "Sa, Si, Su, Se, and So" are set in the
25 index buttons 42. If the index 40 is other than "A, K,
S, T, N, H, M, Y, R, and W", only the index 40 is set
in the index button 42. For example, if "Se" is the

1 index 40, only "Se" is set in the index button 42. After this processing, if "NO" is determined in step S34, the flow advances to step S37, and whether the user activates the end button 26 is checked. If the
5 end button 26 is activated, the "telephone book" program is ended. If the end button 26 is not activated, the flow returns to step S22, and the program processing is repeated from step S22.

An operation of the "card file" program
10 schematically described above with reference to Figs. 8 to 14 will be described below with reference to flow charts in Figs. 17A to 17F.

In step S40, the "card file" menu shown in Fig. 8 is displayed. In step S41, whether the user activates the card read button 63 is checked. If the card read button 63 is activated, whether a card is set at the card inlet 14 is checked in step S42. If the card is set, the flow advances to step S43. In step S43, an image of the card is read by the image scanner 8 and displayed in the card image frame 50. In step S44, a character recognition program based on pattern matching is activated for the card image 50, and recognized characters are displayed in the character recognition result frame 51.

25 Note that the character recognition method based on pattern matching is widely known through a large

1 number of literatures and a detailed description
thereof will be omitted.

In step S45, the characters (a company name, a
division, a title, a personal name, an address, a phone
5 number, and a fax number) in the character recognition
result frame 41 are checked in units of lines, and only
determined characters are set in the columns 55 to 61
in the card data frame 52. After this processing or if
"NO"s are determined in steps S41 and S42, the flow
10 advances to step S46, and whether the user activates
the register button 64 is checked. If the register
button 64 is activated, a data group set in the card
data frame 52 is newly registered in the "card file" as
data of one card. If "NO" is determined in step S46,
15 the flow advances to step S48, and whether the user
activates the image register button 65 is checked. If
the image register button 65 is activated, the data
group set in the card data frame 52 and the card image
50 are newly registered in the "card file" as data of
one card image in step S49, and the flow advances to
step S50. If "NO" is determined in step S48, whether
the user activates one of the character lines in the
character recognition result frame 51 is checked in
step S50. If a line is activated, a tone of the
20 activated line is inverted. If the activated character
line is already inverted, however, the line is returned
to a standard tone. After this processing or if "NO"
25

1 is determined in step S50, the flow advances to step
52, and whether the user activates any of the items 53
in the data frame 52 is checked. If any of the items
53 is activated, whether an inverted character line is
5 present in the character recognition frame 51 is
checked in step S53. If an inverted character line is
present, the inverted line is copied in the activated
item 53 of the card data frame 52 in step S54. In step
S55, the inverted tone in the character recognition
frame 51 is returned to the standard tone, and the flow
10 advances to step S57.

15 If "NO" is determined in step S53, a tone of the
item 53 activated by the user is inverted, and the flow
advances to step S57. If "NO" is determined in step
S52, whether the user activates any of the data lines
54 in the card data frame 52 is checked in step S57.
If any of the data lines 54 is activated, a character
cursor is displayed at the head of the activated line
in step S58. In step S59, the user performs addition
20 and correction of the card data by using the keyboard
5, and the processing in step S59 is continued until a
return key is activated. If the return key is
activated, the flow advances from step S60 to S61, and
a character cursor is erased from the card data frame
25 52. If "NO" is determined in step S57, whether the
user activates the clear button 74 is checked in step
S62. If the clear button 74 is activated, all the data

1 in the card image frame 50, the character recognition
result frame 51, and the card data frame 52 are cleared
in step S63. If "NO" is determined in step S62, the
flow advances to step S64, and whether the user
5 activates the search button 66 is checked. If the
search button 66 is not activated, the flow advances to
step S68. If the search button 66 is activated, data
in the "card file" coincident with characters set in a
part of the card data frame 52 is searched. In this
10 case, if the user activates the search button 66
without setting characters in the card data frame 52,
it is assumed that the user instructs
searching/displaying of all data. In step S66, the
number of searched cases is displayed in the message
15 75. In step S67, the first case of the searched data
is displayed in the card data frame 52.

 If "NO" is determined in step S64, whether the
user activates the next page button 68 is checked in
step S68. If the next page button 68 is not pushed,
20 the flow advances to step S70. If the next page button
68 is activated, however, next data is displayed in
step S69 if a large number of searched data are present
and subsequent data is present after the currently
displayed data, and the flow advances to step S70. In
25 step S70, whether the user activates the preceding page
button 67 is checked. If the preceding page button 67
is activated, preceding data is displayed in step S71

1 if a large number of searched data are present and data
already displayed is present preceding to the currently
displayed data. If "NO" is determined in step S70,
however, whether the user activates the print button 69
5 is checked in step S72. If the print button 69 is
activated, all of the searched data are printed out in
step S73. In step S74, whether the user activates the
correct button 70 is checked. If the correct button is
activated, the flow advances to step S75, and whether
10 the user corrects a part of the card data currently
being searched and displayed is checked. If the card
data is corrected, the corrected card data is
registered in the "card file" in step S76. In this
processing, the corrected data is overwritten on old
15 data. If "NO"s are determined in steps S74 and S75,
whether the user activates the delete button 71 is
checked in step S77. If the delete button 71 is
activated, one case of the currently searched and
displayed card data is deleted from the "card file" in
20 step S78.

If "NO" is determined in step S77, the flow
advances to step S79, and whether the user activates
the call button 73 is checked. If the call button 73
is activated, whether the handset 11a is off-hooked is
checked in step S80. If the handset is off-hooked, the
25 telephone set 11 is instructed to make a call by using
the phone number 60 in the card data frame 52 in step

1 S81. If "NO"s are determined in steps S79 and
S80, whether the user activates the telephone book
button 72 is checked in step S82. If the telephone
book button 72 is not activated, the flow advances to
5 step S92. If the telephone book button ⁷² is activated,
whether the company name 55 or the personal name 58 is
set (both of the company and personal names 55 and 58
can be set) and the phone number 60 or the fax number
61 is set (both of the phone and fax numbers 60 and 61
10 can be set) in the card data frame 52 is checked in
step S83. If this check is determined ^{to be} no good in step
15 S84, the message 75 representing "data is insufficient"
is output in step S85. If the above check is
determined ^{to be} good, the flow advances to step S86, and
whether a tone of only one of the company and personal
names 55 and 58 of the items 53 is inverted and that of
only one of the phone and fax numbers 60 and 61 thereof
is inverted is checked. This result is checked in step
20 S87. If the result is determined ^{to be} no good, the flow
advances to step S88, and the message 75 representing
"which is to be registered ?" is output. If the result
is determined ^{to be} good, whether the company or personal
name 55 or 58 as an objected to be registered in the
25 "telephone book" is accompanied with indication of how
to read is checked in step S89. If the indication of
how to read is not accompanied, the message 75
representing "indicate how to read" is output in step

1 S90. If the indication of how to read is already
 accompanied, a data pair of the company or personal
 name 55 or 58 and the phone or fax name 60 and 61 is
 registered in the "telephone book" in step S91. For
5 example, a pair of "a company name and a telephone
 number" is registered as one case in the "telephone
 book". In step S92, whether the end button 26 is
 activated is checked in step S92. If the end button 26
 is activated, the "card file" program is ended. If the
10 end button 26 is not activated, the flow returns to
 step S41, and the processing from step S41 is
 repeatedly executed.

Fig. 18 is a view showing an analyzing direction
for each line of the image 50 obtained when the
15 character recognition program based on pattern matching
 is executed in step S44 of the flow chart shown in
 Fig. 17.

The processing in step S45 of the flow chart shown
in Fig. 17 will be described below with reference to a
20 flow chart shown in Fig. 19.

In step S100, the number of character lines in the
character recognition result frame 51 is counted to set
a variable n. In step S101, various variables are
initialized. In this case, "1" is set in m
25 representing the number of currently analyzed lines and
 "0" is set in a flag a representing a set state of the
 company name column 52 in the card data frame 52.

COPYRIGHT © 2001 JAPAN TRADE SHOW

1 Similarly, "0"s are set in a flag b for the division
column 56, a flag c for the title column 57, a flag d
for the personal name column 58, a flag e for the
address column 59, a flag f for the phone number column
5 50, and a flag g for the fax number column 61. In step
S102, whether the number of analyzed lines m exceeds
the number of lines n is checked. If the number m
exceeds the number n, the flow is ended. If the number
m does not exceed the number n, the flow advances to
10 step S103, and whether the company name column 55 is
set (a = 0) is checked. If the company name column 55
is already set, the flow advances to step S108. If the
company name column 55 is not set, whether characters
such as "company", "LTD.", "office", or "association"
15 are included on the line m is checked in step S104. If
the characters such as "company" are included, this is
determined in step S105, and the flow advances to step
S106. The line m in the character recognition result
frame 51 is set in the company name column 55 of the
20 card data frame 52, and the variable a = 1 is set to
record that setting in the company name column 55 is
completed.

25 The flow advances to step S107, and if the company
name set in the company name column 55 starts with
katakana or hiraganas, the kana part is automatically
set in the frame for data indicating how to read in the
company name column 55. The flow advances to step

1 S132, the currently analyzed line variable m is
incremented by one, and the flow returns to step S102
of the program, thereby forming a loop for repeating
the processing.

5 If "NO"s are determined in steps S103 and S105,
the flow advances to step S108, and whether the title
column 57 is set ($c = 0$) is checked. If the title
column 57 is not set, whether characters such as
"president", "managing director", "director",
"department manager", "section head", "vice-chief",
"chief clerk", "manager", "chief", or "section chief"
are included on the line m. If it is determined in
step S110 that the above characters are included, the
line m is set in the title column 57 of the card data
frame 52 and the variable $c = 1$ is set in step S111,
and the flow advances to step S132. If "NO"s are
determined in steps S108 and S110, whether the division
name can be set in the division column 56 ($b < 3$) is
checked in step S112. Note that three division names
can be set in this embodiment. This is because a
division name printed on a card is often described over
about three lines.

20 If "YES" is determined in step S112, whether
characters such as "department", "section", "room", or
"charge" are included on the line m is checked in step
S113. If the characters are included, the flow
advances from step S114 to S115. In step S115, the

RECORDED EDITION

1 line m is set in the division column 56 of the card
data frame 52, the variable b is incremented by one,
and the flow advances to step S132.

5 If "NO"s are determined in steps S112 and S114,
whether the personal name 58 column is set ($d = 0$) is
checked in step S116. If the personal name column 58
is not set, an image line on the card image 50
corresponding to the line \underline{m} is compared with the rest
in step S117. If the line \underline{m} is widest, the flow
advances from step S118 to S119. In step S119, the
line \underline{m} is set in the personal name column 58 of the
card data frame 52, $d = 1$ is set, and the flow advances
to step S132. Whether the line \underline{m} is a personal name
line is checked on the basis of the width of an image
15 line because a line of "personal name" is widest on
many cards.

If "NO"s are determined in steps S116 and S118, whether the address column 59 is set ($e = 0$) is checked in step S120. If the address column 59 is not set, whether a "〒" mark or a prefectoral name is included on the line m is checked in step S121. If the "〒" mark or the prefectoral name is included, the flow advances from step S122 to S123. In step S123, the line m is set in the address column 59 of the card data frame 52, $e = 1$ is set, and the flow advances to step S132. If "NO"s are determined in steps S120 and S122, the flow advances to step S124, and whether the phone number

1 column 60 is set ($f = 0$) is checked. If the phone
number column 60 is not set, whether a "telephone",
"TEL" or a "~~T~~" mark followed by numerals is included on
the line \underline{m} is checked in step S125. If followed, the
5 flow advances from step S126 to S127. In step S127,
only the numerals on the line \underline{m} are set in the phone
number column 60, and "1" is set in the variable \underline{f} .
The flow then advances to step S132.

If "NO"s are determined in steps S124 and S126,
10 the flow advances to step S128. If the fax number
column 61 in the card data frame 52 is not set ($g = 0$)
in step S128, whether characters of "facsimile" or
"FAX" followed by numerals are included on the line \underline{m}
is checked in step S129. If followed, the flow
15 advances from step S130 to S131. In step S131, only
the numerals on the line \underline{m} are set in the fax number
column 61 of the card data frame 52, and "1" is set in
the variable \underline{g} . The flow advances to step S132, the
currently analyzed line variable \underline{m} is incremented by
20 one, and the flow returns to step S102 of the program,
thereby forming a loop.

In this embodiment, a card is laterally placed and
character recognition for a laterally written card is
performed. However, it is a matter of course that a
25 card can be vertically placed and character recognition
and analysis for a vertically written card can be

1 performed. In addition, a card written in English can
be analyzed.

5 In this embodiment, both the telephone book and
the card file enable automatic calling of a "telephone
number". However, a "facsimile number" can be
similarly called in accordance with the telephone book
and the card file. For example, when the telephone
book is called in order to perform facsimile
transmission, only a customer registered by a
10 "facsimile number" can be displayed while a customer
registered by a telephone number is highlighted,
thereby alarming a user that the telephone number
cannot be used. Furthermore, an ^{edited} _{edit} document
processed by a wordprocessor can be directly
15 transmitted by a facsimile by performing automatic
calling utilizing the telephone book or card file.

Fig. 20 is a flow chart for explaining a
transmission operation performed by a facsimile
function utilizing the above data base.

20 When a FAX transmission program is activated, a
file to be transmitted is designated (S151). A
document to be transmitted is stored in the file to be
transmitted, thereby forming a transmission data file.

25 A search key word for the above telephone book
file as a data base is input (S152). For example, this
search key word can be input by "0000" as shown in
Fig. 13.

DEPARTMENT OF STATE
2001

1 The telephone book file is searched by the search
key word to call and display corresponding customer
data on the CRT display 3 as shown in Fig. 14 (S153).

5 Upon selection by an operator, a customer to which
data is to be actually transmitted is designated from
the customer data displayed on the CRT display 3, and a
FAX transmission list file is formed (S154). In this
case, the operator can select a plurality of customers.

10 On the basis of the FAX transmission list file,
the contents of the transmission data file are
transmitted to the designated customer (S155).

15 Fig. 21 is a schematic view for explaining a
relationship between the contents of a telephone book
file 155, the search key word, and a FAX transmission
list file 156.

20 The telephone ^{book} _{book} file 155 stores, in addition to
a large number of customer data, customer data of a xx
corporation and its associated companies such as "xx
corporation", "xx corporation ΔΔ branch office", and
"corporation xx service". By inputting "xx" as the
search key word, only customer data of the "xx
corporation and its associated companies are searched
from a large number of customer data and stored in the
FAX transmission list file 156. If necessary, the
contents of the FAX transmission data file 156 are
deleted or added to select only data to be transmitted.

00013543-00000000
A

1 By selecting a suitable search key word as
described above, necessary customer data can be easily
searched.

5 Therefore, since multi-address communication can
be very easily performed by using customer data in the
telephone book file, a registration table for
multi-address communication need not be additionally
provided to solve a problem of a cumbersome operation.

10 In recent years, a card is often printed such that
its upper surface is printed in Japanese while its
lower surface is printed in English. Therefore, two
image scanners for upper and lower surfaces can be
connected to perform image reading of both the surfaces
at the same time to execute character recognition of
15 both the surfaces, thereby forming both the surfaces
into card data bases. At this time, if pronunciations
of English words are converted into kanas, data
indicating how to read a company name and a personal
name written in Japanese on the upper surface can be
automatically set, thereby reducing a load on a user.
20 In addition, especially when a map is printed on the
lower surface instead of an English card, card file
image registration effectively functions.

25 In the above embodiment, only a card has been
described as an object to be processed. However, a
document of a fixed form having definite contents such
as a postcard for invitation can be subjected to image

1 reading, character recognition, and data base
formation.

In the above embodiment, card image registration
can be performed in the "card file". However,
5 processing can be performed such that a card image is
corrected by an image editor program before
registration, a simple map or the like is added, and
then image registration is executed. In this case, the
image editor program is stored in the auxiliary
10 storage.

In the above embodiment, the present invention has
been described with reference to the information
processing apparatus having a plurality of functions
such as a personal computer function, a telephone
function, a facsimile function, and a wordprocessor
function. As a simplest application form of the
15 present invention, however, telephone sets as shown in
Figs. 22 and 28 can be made.

Referring to Fig. 22, a telephone set 77 includes
20 a handset 78, push buttons 79, and a liquid crystal
display 80 for displaying a phone number and a time.
These parts are arranged similarly to those of a
conventional telephone set.

Display buttons 81 and 82 are located at the side
25 of the liquid crystal display 80. The display buttons
81 and 82 are for selecting a phone number displayed on
the liquid crystal display 80. That is, this

03013457-020100
65

1 embodiment optically reads a phone number of a card,
recognizes it, and uses it for calling. However, a
plurality of phone numbers of, e.g., a home, a main
office, and a branch office are often described on a
5 card. Therefore, two of the phone numbers are read,
recognized, and displayed on the display 80, and one of
the two numbers is selected by the display buttons 81
and 82.

10 The telephone set 77 also has a card inlet (to be
referred to as a slot hereinafter) 83. The slot 83 is
for inserting a card whose phone number is to be read
and has a mechanism for transporting and optically
reading a card.

15 The telephone set 77 has, at its rear portion, a
telephone line 84 for communication and a power source
cable 85 for supplying power to the telephone set.

Fig. 23 shows a control system incorporated in the
telephone set shown in Fig. 22.

20 Referring to Fig. 23, a telephone set circuit 86
includes a voice signal amplifying section for the
handset 78, an input circuit for the push buttons 79, a
line controller, a power source circuit, and the like.
An arrangement of the telephone set circuit 86 is
similar to that of a conventional circuit. Note that
25 the telephone set circuit 86 incorporates, in addition
to the above circuits, a known dialing circuit for

1 sending a dial signal corresponding to input phone
number data onto a line.

A central processing unit (to be referred as a CPU hereinafter) 87 for controlling the entire apparatus is connected to a control memory 88.

The memory 88 is divided into two parts, a ROM 88a and a RAM 88d. The ROM 88a stores a control program 88b and a display character font 88c. The RAM 88d includes a storage area 88e for developing and storing a dot image of a card, storage areas 88f and 88g for recording a phone number, and a storage area 88h for storing data for programs.

The CPU 87 is also connected to the following members to be controlled besides the memory 88.

15 That is, members 89 to 92 are for reading a phone number of a card. An image sensor 89 is constituted by a CCD line sensor or the like. A card transporter 90 accomodates a card into the apparatus or delivers it therefrom. A sensor 91 detects whether a card is inserted in the slot. A sensor 92 detects whether accomodation of a card into the apparatus is completed. These circuits and mechanisms are arranged around the slot 83 as will be described later.

The liquid crystal display 80 for displaying a
25 phone number has a two-line width and is connected via
a known display controller or the like (not shown).

1 The display buttons 81 and 82 are for selecting a
first or second one of two phone numbers displayed on
two display lines of the display 80, thereby performing
automatic calling.

5 Fig. 24 shows an arrangement of the image sensor
89, the card transporter 90, and the like inside the
slot 83 of the telephone set 77.

When a card 93 is inserted from the slot 83 by an operator, the sensor 91 detects the leading edge of the card 93, and driving of eight transport rollers 90a (driven by a motor or the like (not shown) of the card transporter 90) constituting the card transporter 90 is started. The card 93 is accommodated to the left of Fig. 24 at a constant speed, while an image of the card 93 is read by the image sensor 89 located at a central portion of the rollers 90a and stored in the memory 88.

When the card 93 is accommodated to a certain degree, the sensor 92 detects the leading edge of the card 93, and reverse rotation of the transport rollers 90a is started. Finally, the card 93 is delivered from the slot 83, and a read operation is completed. Note that the sensors 91 and 92 are constituted by reflecting photosensors or the like.

An operation of the above arrangement will be described below with reference to flowcharts in Figs. 25A to 25C. Procedures shown in Figs. 25A to 25C are stored in the ROM 88a of the memory 88 as

1 programs of the CPU 87 and started when the telephone
set 77 is connected to the power source cable 85 and
power supply to the apparatus is started.

When power supply to the apparatus is started, the
5 CPU 87 checks in step S160 of Fig. 25A whether the
handset 78 is off-hooked. If the hand-set is not
off-hooked, the flow loops and waits.

If the hand-set 78 is off-hooked, the flow advances to step S161, and whether a card is inserted in the slot 83 is checked by detecting a change in output signal from the sensor 91. If the card 93 is not inserted, the flow returns to step S160 and loops. If the card is inserted, the flow advances to step S162, and the transporter 90 is instructed to accomodate the card.

Note that an operator inserts the card in the slot 83 so that a surface on which a phone number is described or printed faces the image sensor 89. At this time, as indicated by arrows shown in Figs. 26A and 26B, the card is inserted in the slot 83 such that the head of a line of the card is set toward a predetermined direction (in this case, coincident with an insertion direction) regardless of whether the card is laterally written (Fig. 26A) or vertically written (Fig. 26B).

When the card 93 is inserted in the slot 83, the transport rollers 90a start rotating at a constant

卷之三

1 speed in step S163, thereby accomodating the card 93.

5 The image sensor 89 reads a printed image on the card with predetermined resolution, and read binary data is developed and stored in the card image storage area 88e on the RAM 88d of the memory 88. This operation is continuously executed until the sensor 92 detects the leading edge of the card 93 in step S164.

10 When image reading of the card is completed, the flow advances to step 165, and the card transporter 90 is instructed to deliver the card. The transport rollers 90a start rotating in the reverse direction to deliver the card 93 from the slot 83.

15 In step S166 of Fig. 25B, the storage area 88f for a phone No. A and the storage area 88g for a phone No. B of the RAM 88d are cleared. In step 167, "1" is set in a counter variable "n". The counter variable "n" is for reading up to two phone numbers from the same card and takes two values "1" and "2" representing the number of reading times of a phone number.

20 In step S168, data in the storage area 88e for image data is searched in units of lines. In this case, as shown in Figs. 27A and 27B, a direction along which characters continue corresponding to the longitudinal direction of the card 93 is considered as a direction of "line" regardless of whether the card is laterally or vertically written. In a direction indicated by reference symbol Sr, a line including

00011000 00000000 00000000 00000000

1 characters such as "telephone", "TEL", vertically
written "telephone" or a mark representing a telephone
set is searched by a known pattern matching method of
character recognition (OCR). Note that if $n = 2$ in
5 step S168, i.e., if searching is to be performed for
the second time, lines outside those searched for the
first time are searched.

If a line including characters such as "telephone"
or a mark is found in step S168, the flow advances from
10 step S169 to S170. If a corresponding line is not
found, the flow advances to step S172. In step S172,
an alphanumeric image following "telephone" or a
kanji/numeral image following vertically written
"telephone" is analyzed by the pattern matching method
15 of OCR, thereby obtaining a code train (e.g., an ASCII
code) representing a phone number. The pattern
matching method of OCR is well known and a detailed
described thereof will be omitted. The OCR processing
may be performed by the CPU 87 or another recognition
20 control system.

In step S171, whether the counter variable "n"
satisfies $n = 1$, i.e., whether searching is performed
for the first time is checked. If searching is
performed for the first time, the code train obtained
25 in step S170 is stored in the storage area 88f of the
RAM 88d, and $n = 2$ is set as the counter variable "n"

1 in step S174. The flow then returns to step S168 to start an operation for obtaining a second phone number.

5 If the counter variable "n" does not satisfy $n = 1$ in step S171, the flow advances to step S175, and the code train obtained in step S170 is stored in the storage area 88g of the RAM 88d.

10 In step S176, the phone number data in the storage areas 88f and 88g are displayed on the display 80 by using the data stored in the character font storage area 88c of the ROM 88a.

15 If characters such as "telephone" are not found in step S169, the flow advances to step S172. If $n = 1$, i.e., if characters are not found by first searching, the flow returns to the start of the program and waits until another card is inserted in the slot 83. If $n = 2$, i.e., if characters are not found by second searching, the phone number is displayed on the display 80 in step S176. At this time, the storage area 88g is cleared.

20 The flow then advances to step S177 in Fig. 25(c). If an operator activates the display button 81, the telephone set circuit 86 is instructed to perform calling in accordance with the phone number stored in the storage area 88f, and the flow returns to the start of the program, thereby ending the processing. The dialing circuit of the telephone set circuit 86 transmits a dial signal corresponding to the input

1980 RELEASE UNDER E.O. 14176

1 phone number represented by a character code such as an
5 ASCII code or binary data to the telephone line.

10 If it is determined that the display button 81 is
5 not activated, the flow advances to step S179. If the
display button 82 is activated, the telephone set
circuit 86 is instructed to perform calling by using
the phone number data stored in the storage area 88g in
step S180, and the flow returns to the start of the
program, thereby ending the processing.

15 If a trunk code of the telephone set 77 stored in
a part of the memory 88 coincides with a trunk code of
a customer, phone number data without the trunk code is
supplied to the dialing circuit of the telephone set
circuit 86, and dial processing is performed on the
basis of this data.

20 If it is determined in step S179 that the display
button B 82 is not activated, the flow advances to step
25 S181, and whether the new card 93 is inserted in the
slot 83 is checked. If the card 93 is inserted, the
flow returns to the start of the program to execute the
reading processing for the card 93 again.

25 If the card 93 is not inserted, the flow advances
to step S182, and whether the handset 78 is returned to
an ON hook state is checked. If the handset 78 is not
returned to the ON hook state, the flow returns to step
S177 to repeat determinations in steps S177, S179,
S181, and S182. If it is determined that the handset

1 78 is returned, the flow returns to the start of the
program and waits.

According to the above telephone set, character
data following characters such as "telephone" is
5 optically read, recognized, and used to perform
calling. Therefore, unlike in a conventional
apparatus, even if phone number data is not described
nor printed on a predetermined position by a special
recording system such as a bar code, phone number data
10 can be read from any type of a card, and calling can be
automatically performed on the basis of the read data,
thereby simplifying a calling operation and preventing
an operational error. In particular, since a phone
number can be read and recognized regardless of whether
15 it is laterally or vertically written, the present
invention has high versatility.

In addition, a plurality of phone numbers of a
card can be read and recognized, and a desired one of
the phone numbers can be selected by a simple button
20 operation. Therefore, phone number information
described on a card can be utilized substantially
similarly to a case of manual calling.

Still another embodiment in which the present
invention is applied to a telephone set will be
25 described below. This embodiment is a telephone set
for reading and recognizing a phone number on a
document or printed matter not a card but various types

DEUTSCHE PEGEDE

1 of leaflets or pamphlets and using it to perform
calling.

A difference between telephone sets shown in
Figs. 22 and 28 is that a display area of a display 80
5 has a size of three lines and therefore can display
three phone numbers and three display buttons 94 to 96
are provided to select one of three phone numbers
accordingly.

The apparatus shown in Fig. 28 has an image sensor
10 97 on the upper surface of the apparatus as a reading
mechanism. The image sensor 97 is constituted by a
two-dimensional CCD sensor or the like and arranged to
read image data on a portion corresponding to a hatched
area shown in Fig. 28 of a document or printed matter
15 placed to face downward on the image sensor 97. A read
timing of the image sensor 97 is determined by
activation of a read start button 98.

Push buttons 79 and the display buttons 94 to 96
20 are embedded in the apparatus such that their upper end
faces are set lower than the surface of the apparatus.
Therefore, when a user sets a document or printed
matter on the image sensor 97, erroneous activation of
buttons by the user can be prevented.

Fig. 29 shows an arrangement of a control system
25 of the apparatus shown in Fig. 28. The circuit shown
in Fig. 29 has substantially the same arrangement as
that of the circuit shown in Fig. 23 except that the

1 image sensor 97 is of a fixed type; three display
2 buttons 94 to 96 are used, and three data areas 881 to
3 883 for a phone number are formed in a RAM 88d
4 accordingly; and the image sensor 97 of an original
5 fixed type does not transport an original unlike in the
above embodiment but reads image data in the
two-dimensional read area and is constituted by an
optical system, a two-dimensional image sensor, and the
like.

10 Operations of the above arrangement will be
described below with reference to flowcharts shown in
Figs. 30A and 30B. Note that this program is
started when a power source is connected to the
telephone set 77.

15 In step S190 of Fig. 30A, whether the read start
button 98 is activated is checked. If the read start
button 98 is activated, a read/analysis routine of an
original such as a document or printed matter is
started from step S191. Note that an operator places
20 the original on the image sensor 97 such that a line
direction of characters coincides with the longitudinal
direction (lateral direction in Fig. 28) of the image
sensor 97 and activates the read start button 98 at a
desired timing.

25 In step S191, the image sensor 97 is started. In
step S192, an image of the original placed on the image
sensor 97 is read by the image sensor 97 and developed

1 and stored as binary data in a printed image area 88e
of the RAM 88d of the memory 88.

5 In step S193, the storage area 88e is searched and
analyzed in units of lines by a pattern matching method
of character recognition (OCR) as in the above
embodiment, thereby obtaining a maximum of three phone
numbers. The processing in step S193 will be described
in detail later.

10 In step S194, the obtained phone number data are
stored in the phone number storage areas 881 to 883 of
the RAM 88d. If the number of the obtained phone
numbers is less than three in step S193, phone Nos. A,
B, and C are cleared accordingly.

15 In step S195, the areas 881 to 883 of the RAM 88d
are displayed on the display 80, and the flow returns
to the start of the program and waits until the user
activates the display buttons 94 to 96. This state is
similar to that in the above embodiment except that
three phone numbers are displayed on the display 80.

20 If it is determined in step S190 that the read
start button 98 is not activated, the flow advances to
step S196. If the handset 78 is not off-hooked in step
S196, the flow loops and waits for another instruction
from the user.

25 If it is determined in step S196 that the handset
78 is off-hooked, the flow advances to step S197 in
Fig. 30B.

1 Step S197, S200, or S203 is for checking
activation of a corresponding one of the display
buttons 94 to 96. If any of the display buttons 94 to
96 is activated, the flow advances to a corresponding
5 one of steps S198, S201, and S204.

In each of steps S198, S201, and S204, whether a
phone number is stored in one of the storage areas 881
10 to 883 corresponding to the display buttons 94 to 96,
respectively. If a phone number is not stored, the
flow returns to step S190 in Fig. 30A.

If a phone number is stored in any of steps S198,
S201, and S204, the flow advances to a corresponding
one of steps S199, S202, and S205, and phone number
data stored in a corresponding one of the ares 881 to
15 883 is supplied to the telephone set circuit 86,
thereby performing calling as described above. As in
the above embodiment, if a trunk code of the telephone
set coincides with that of a customer, a phone number
without the trunk code is used.

20 In this manner, calling can be performed for a
customer by using phone number data read from any type
of a document or printed matter by the image sensor 97
and subjected to character recognition. Figs. 31A
and 31B show in detail the read processing in step
25 S193 of Fig. 30A.

1 In step S206, arrays TELA, TELB, and TELC set in a
work area of a memory for temporarily registering a
phone number are cleared, and "0" is set in a counter.

5 In step S207, binary image data in the storage
area 88e is searched in units of lines by a pattern
matching method of OCR to find a line including
characters such as "telephone", "TEL", vertically
written "telephone" or a mark representing a telephone
set. As in the case shown in Fig. 27, a search
10 direction coincides with an arranging direction of
characters of the original. In addition, the counter
variable "n" is reset as described above. In this
case, however, the counter variable "n" is controlled
to extract three phone numbers.

15 If $n = 1$ is determined in step S207, i.e., if
searching is to be performed for the second time, lines
outside those searched when $n = 0$, i.e., upon first
searching are searched. If $n = 2$, i.e., upon third
searching, lines outside those searched when $n = 0$ and
20 $n = 1$, i.e., upon first and second searchings are
searched. If a line including characters such as
"telephone" are found in step S207, the flow advances
from step S208 to step S209. If a corresponding line
is not found, this subroutine returns to the main
25 routine and ends.

 In step S209, as in the above embodiment, an
alphanumeric image following "telephone" or the like or

1 a kanji/numeral image following vertically written
"telephone" is analyzed by the pattern matching method
of OCR, thereby obtaining a code train corresponding to
the phone number.

5 In step S210, whether $n = 0$ is satisfied, i.e.,
whether searching is to be performed for the first time
is checked. If searching is to be performed for the
first time, the code train obtained in step S209 is set
in the array TELA in step S211. Similarly, the code
10 train is set in the array TELB in steps S212 and S213
if $n = 1$, and the code train is set in the array TELC
in steps S214 and S215 if $n = 2$.

15 After the code train is set, the flow advances to
step S216 in Fig. 31B, and the counter n is counter
up. If it is determined in step S217 that the counter
 n is two or less, the flow returns to step S121, and
searching of a phone number is executed again. If the
counter n is larger than two (i.e., three phone numbers
are already read), the processing is ended, and the
20 flow returns to the routine shown in Fig. 30A.
Thereafter, data of the arrays TELA, TELB, and TELC are
transferred to the storage areas 881 to 883,
respectively.

25 In this manner, up to three phone number data can
be read and recognized.

In the above embodiment, an arranging direction of
lines of an original must be aligned with the

1 longitudinal direction of the image sensor 97. In
order to easily perform this positioning, a matrix
pattern 97a as shown in Fig. 32 may be printed or
marked on the upper surface of the telephone set 77.

5 By aligning a corner or side of an original with the
matrix pattern 97a, an operator can set a printed
matter on the upper surface of the image sensor 97
without a skew.

10 The present invention can be applied not only to a
telephone set but also to a facsimile apparatus.

15

20

25

1 WHAT IS CLAIMED IS:

Sub E1-AT

1. An information processing apparatus comprising:
5 reading means for reading image information including character data such as a phone number recorded in a recording medium;
10 recognizing means for recognizing the character data in the image information read by said reading means;
registering means for registering the character data recognized by said recognizing means;
15 searching means for searching a desired phone number from the character data registered in said registering means; and
control means for performing communication processing on the basis of the phone number searched by said searching means.

2. An apparatus according to claim 1, further comprising display means for displaying the image information read by said reading means and the character data recognized by said recognizing means.

Sub N1-2

3. An apparatus according to claim 1, wherein the character data recognized by said recognizing means is registered in said registering means in accordance with 25 a type of the character data.

Sub L2

4. An apparatus according to claim 1, further comprising:

1 display means for displaying the character data
registered in said registering means in accordance with
a type of the character data; and
means for correcting and changing the character
data displayed on said display means.

5. An apparatus according to claim 1, wherein
said control means performs control of making a phone
call on the basis of the phone number searched by said
searching means.

10 6. An apparatus according to claim 1, further
comprising storage means for storing a document to be
transmitted,

15 wherein said control means performs control of
transmitting the document to be transmitted stored in
said storage means on the basis of the phone number
searched by said searching means.

7. An information processing apparatus
comprising:
reading means for reading phone number information
recorded in a recording medium;
storage means for storing a plurality of pieces of
phone number information read by said reading means;
selecting means for selecting one of the pieces of
phone number information stored in said storage means;
25 and

1 control means for performing communication
processing on the basis of the phone number selected by
said selecting means.

5 8. An apparatus according to claim 7, further
comprising display means for displaying the phone
number information read by said reading means.

10 *Hand No* 9. An apparatus according to claim 7, wherein
said control means performs control of making a phone
call on the basis of the phone number selected by said
selecting means.

15 10. An apparatus according to claim 7, wherein
said reading means is located on an upper surface of a
main body of said information processing apparatus.

11. An apparatus according to claim 8, wherein
15 said display means comprises a liquid crystal display
device.

20





1 ABSTRACT OF THE DISCLOSURE:

An information processing apparatus includes a reading unit, a recognizing unit, a registering unit, a searching unit, and a control unit. The reading unit reads image information including character data such as a phone number recorded in a recording medium. The recognizing unit recognizes the character data in the image information read by the reading unit. The registering unit registers the character data recognized by the recognizing unit. The searching unit searches a desired phone number from the character data registered in the registering unit. The control unit performs communication processing on the basis of the phone number searched by the searching unit.

15


20

25

08/035Y3

17/383079

FIG. 1



08/013543

~~17383073~~






FIG. 2



08/03543

~~1733079~~


FIG. 3



08/03/543

APPLICANT	CLASS	FIG.
GRAFTMAN	CLASS	SUBCLASS


FIG. 4



08/013543

~~11/383079~~

FIG. 5



7/333079

08/03/63

FIG. 7







FIG. 6



08/03543

~~1/333979~~

FIG. 8



08/013543

~~11/388079~~

FIG. 9

F/G. 10

SEARCH	PRINT	REGISTER
CLASS	SUBCLASS	ITEM NO.
SEARCH	PRINT	REGISTER
DATA	MAN	ITEM NO.

08/013543
~~17/08/013543~~

3.4

50	55	53	52	54
26				
				
56	COMPANY NAME	CLEAR		
57	DIVISION	74		
58	TITLE			
59	PERSONAL NAME			
60	ADDRESS	xx x OHTA OHTA-KU TOKYO 〒001		
61	PHONE NO.	(xx) 000-xxxx		
62	FAX NO.	(xx) 444-0000		
63	MEMO			
64	SEARCH	71		
65	IMAGE	70		
66	PRECEDING	69		
67	NEXT	68		
68	PRINT	72		
69	CORRECT	73		
70	DELETE			
71	CALL			
72	TELEPHONE BOOK			
73				
51	50			
52	53			
53	54			
54	55			
55	56			
56	57			
57	58			
58	59			
59	60			
60	61			
61	62			
62	63			
63	64			
64	65			
65	66			
66	67			
67	68			
68	69			
69	70			
70	71			
71	72			
72	73			
73				
74				

OFFICE EQUIPMENT SYSTEM CENTER
 ☐ x ☐ DEVELOPMENT DEPT
 ☐ x ☐ 1ST DESIGN SECT
 FURUYA YOJI
 ☐ x ☐ CORPORATION TEL (03) 000 xxxx
 x-x-x FAX (03) 444 0000
 OHTA OHTA-KU TOKYO 〒001

OFFICE EQUIPMENT SYSTEM CENTER
 ☐ x ☐ DEVELOPMENT DEPT
 ☐ x ☐ 1ST DESIGN SECT
 FURUYA YOJI
 ☐ x-x CORPORATION TEL (03) 000 xxxx
 FAX (03) 444-0000
 OHTA OHTA-KU TOKYO 〒001

READ

REGISTER

IMAGE

SEARCH

PRECEDING

NEXT

PRINT

CORRECT

DELETE

CALL

TELEPHONE BOOK

08/013543

SEARCHED	INDEXED	FILED
SERIALIZED	CLASS	SUPERASS
DRAFTSMAN		

FIG. 11A

58 ↗

	NAME	
		FURUYA YOJI

FIG. 11B

58 ↗

	NAME	furu ya yohji ↗
		FURUYA YOJI

08/013543

~~07/388079~~

FIG. 12

		26	50	55	53	52	54
		56	57	58	59	60	61
		62	63	64	65	66	67
		68	69	70	71	72	73
		74	75	76	77	78	79
		80	81	82	83	84	85
		86	87	88	89	90	91
		92	93	94	95	96	97
		98	99	100	101	102	103
		104	105	106	107	108	109
		110	111	112	113	114	115
		116	117	118	119	120	121
		122	123	124	125	126	127
		128	129	130	131	132	133
		134	135	136	137	138	139
		140	141	142	143	144	145
		146	147	148	149	150	151
		152	153	154	155	156	157
		158	159	160	161	162	163
		164	165	166	167	168	169
		170	171	172	173	174	175
		176	177	178	179	180	181
		182	183	184	185	186	187
		188	189	190	191	192	193
		194	195	196	197	198	199
		200	201	202	203	204	205
		206	207	208	209	210	211
		212	213	214	215	216	217
		218	219	220	221	222	223
		224	225	226	227	228	229
		230	231	232	233	234	235
		236	237	238	239	240	241
		242	243	244	245	246	247
		248	249	250	251	252	253
		254	255	256	257	258	259
		260	261	262	263	264	265
		266	267	268	269	270	271
		272	273	274	275	276	277
		278	279	280	281	282	283
		284	285	286	287	288	289
		290	291	292	293	294	295
		296	297	298	299	300	301
		302	303	304	305	306	307
		308	309	310	311	312	313
		314	315	316	317	318	319
		320	321	322	323	324	325
		326	327	328	329	330	331
		332	333	334	335	336	337
		338	339	340	341	342	343
		344	345	346	347	348	349
		350	351	352	353	354	355
		356	357	358	359	360	361
		362	363	364	365	366	367
		368	369	370	371	372	373
		374	375	376	377	378	379
		380	381	382	383	384	385
		386	387	388	389	390	391
		392	393	394	395	396	397
		398	399	400	401	402	403
		404	405	406	407	408	409
		410	411	412	413	414	415
		416	417	418	419	420	421
		422	423	424	425	426	427
		428	429	430	431	432	433
		434	435	436	437	438	439
		440	441	442	443	444	445
		446	447	448	449	450	451
		452	453	454	455	456	457
		458	459	460	461	462	463
		464	465	466	467	468	469
		470	471	472	473	474	475
		476	477	478	479	480	481
		482	483	484	485	486	487
		488	489	490	491	492	493
		494	495	496	497	498	499
		500	501	502	503	504	505

08/013543

~~07/388079~~

FIG. 13




FIG. 14


08/013543
17/388073

26	50	55	53	52	54
<input type="checkbox"/>	OFFICE EQUIPMENT SYSTEM CENTER OXA DEVELOPMENT DEPT OXA 1ST DESIGN SECT FURUYA YOJI OOOO CORPORATION x-x-x OHTA-OHTA-KU TOKYO 〒001 TEL (03) 000-XXXX FAX (03) 444-0000	COMPANY NAME OOOO CORPORATION	714	OFFICE EQUIPMENT SYSTEM CENTER --- 1ST DESIGN SECTION	
56	57	58	59	60	61
TITLE	PERSONAL NAME FURUYA YOJI	ADDRESS x x x OHTA OHTA-KU TOKYO 〒001 PHONE NO. (44) 000-XXXX	FAX NO. (xx) 444-0000	MEMO SE FOR 4 YEARS: EXPERT IN JAPANESE LANGUAGE PROCESSING	72
62	63	64	65	66	67
62	63	64	65	66	67
63	64	65	66	67	68
63	64	65	66	67	69
63	64	65	66	67	70
63	64	65	66	67	71
63	64	65	66	67	72
63	64	65	66	67	73
63	64	65	66	67	74
63	64	65	66	67	75
63	64	65	66	67	76
63	64	65	66	67	77
63	64	65	66	67	78
63	64	65	66	67	79
63	64	65	66	67	80
63	64	65	66	67	81
63	64	65	66	67	82
63	64	65	66	67	83
63	64	65	66	67	84
63	64	65	66	67	85
63	64	65	66	67	86
63	64	65	66	67	87
63	64	65	66	67	88
63	64	65	66	67	89
63	64	65	66	67	90
63	64	65	66	67	91
63	64	65	66	67	92
63	64	65	66	67	93
63	64	65	66	67	94
63	64	65	66	67	95
63	64	65	66	67	96
63	64	65	66	67	97
63	64	65	66	67	98
63	64	65	66	67	99
63	64	65	66	67	100
63	64	65	66	67	101
63	64	65	66	67	102
63	64	65	66	67	103
63	64	65	66	67	104
63	64	65	66	67	105
63	64	65	66	67	106
63	64	65	66	67	107
63	64	65	66	67	108
63	64	65	66	67	109
63	64	65	66	67	110
63	64	65	66	67	111
63	64	65	66	67	112
63	64	65	66	67	113
63	64	65	66	67	114
63	64	65	66	67	115
63	64	65	66	67	116
63	64	65	66	67	117
63	64	65	66	67	118
63	64	65	66	67	119
63	64	65	66	67	120
63	64	65	66	67	121
63	64	65	66	67	122
63	64	65	66	67	123
63	64	65	66	67	124
63	64	65	66	67	125
63	64	65	66	67	126
63	64	65	66	67	127
63	64	65	66	67	128
63	64	65	66	67	129
63	64	65	66	67	130
63	64	65	66	67	131
63	64	65	66	67	132
63	64	65	66	67	133
63	64	65	66	67	134
63	64	65	66	67	135
63	64	65	66	67	136
63	64	65	66	67	137
63	64	65	66	67	138
63	64	65	66	67	139
63	64	65	66	67	140
63	64	65	66	67	141
63	64	65	66	67	142
63	64	65	66	67	143
63	64	65	66	67	144
63	64	65	66	67	145
63	64	65	66	67	146
63	64	65	66	67	147
63	64	65	66	67	148
63	64	65	66	67	149
63	64	65	66	67	150
63	64	65	66	67	151
63	64	65	66	67	152
63	64	65	66	67	153
63	64	65	66	67	154
63	64	65	66	67	155
63	64	65	66	67	156
63	64	65	66	67	157
63	64	65	66	67	158
63	64	65	66	67	159
63	64	65	66	67	160
63	64	65	66	67	161
63	64	65	66	67	162
63	64	65	66	67	163
63	64	65	66	67	164
63	64	65	66	67	165
63	64	65	66	67	166
63	64	65	66	67	167
63	64	65	66	67	168
63	64	65	66	67	169
63	64	65	66	67	170
63	64	65	66	67	171
63	64	65	66	67	172
63	64	65	66	67	173
63	64	65	66	67	174
63	64	65	66	67	175
63	64	65	66	67	176
63	64	65	66	67	177
63	64	65	66	67	178
63	64	65	66	67	179
63	64	65	66	67	180
63	64	65	66	67	181
63	64	65	66	67	182
63	64	65	66	67	183
63	64	65	66	67	184
63	64	65	66	67	185
63	64	65	66	67	186
63	64	65	66	67	187
63	64	65	66	67	188
63	64	65	66	67	189
63	64	65	66	67	190
63	64	65	66	67	191
63	64	65	66	67	192
63	64	65	66	67	193
63	64	65	66	67	194
63	64	65	66	67	195
63	64	65	66	67	196
63	64	65	66	67	197
63	64	65	66	67	198
63	64	65	66	67	199
63	64	65	66	67	200
63	64	65	66	67	201
63	64	65	66	67	202
63	64	65	66	67	203
63	64	65	66	67	204
63	64	65	66	67	205
63	64	65	66	67	206
63	64	65	66	67	207
63	64	65	66	67	208
63	64	65	66	67	209
63	64	65	66	67	210
63	64	65	66	67	211
63	64	65	66	67	212
63	64	65	66	67	213
63	64	65	66	67	214
63	64	65	66	67	215
63	64	65	66	67	216
63	64	65	66	67	217
63	64	65	66	67	218
63	64	65	66	67	219
63	64	65	66	67	220
63	64	65	66	67	221
63	64	65	66	67	222
63	64	65	66	67	223
63	64	65	66	67	224
63	64	65	66	67	225
63	64	65	66	67	226
63	64	65	66	67	227
63	64	65	66	67	228
63	64	65	66	67	229
63	64	65	66	67	230
63	64	65	66	67	231
63	64	65	66	67	232
63	64	65	66	67	233
63	64	65	66	67	234
63	64	65	66	67	235
63	64	65	66	67	236
63	64	65	66	67	237
63	64	65	66	67	238
63	64	65	66	67	239
63	64	65	66	67	240
63	64	65	66	67	241
63	64	65	66	67	242
63	64	65	66	67	243
63	64	65	66	67	244
63	64	65	66	67	245
63	64	65	66	67	246
63	64	65	66	67	247
63	64	65	66	67	248
63	64	65	66	67	249
63	64	65	66	67	250
63	64	65	66	67	251
63	64	65	66	67	252
63	64	65	66	67	253
63	64	65	66	67	254
63	64	65	66	67	255
63	64	65	66	67	256
63	64	65	66	67	257
63	64	65	66	67	258
63	64	65	66	67	259
63	64	65	66	67	260
63	64	65	66	67	261
63	64	65	66	67	262
63	64	65	66	67	263
63	64	65	66	67	264
63	64	65	66	67	265
63	64	65	66	67	266
63	64	65	66	67	267
63	64	65	66	67	268
63	64	65	66	67	269
63	64	65	66	67	270
63	64	65	66	67	271
63	64	65	66	67	272
63	64	65	66	67	273
63	64	65	66	67	274
63	64	65	66	67	275
63	64	65	66	67	276
63	64	65	66	67	277
63	64	65	66	67	278
63	64	65	66	67	279
63	64	65	66	67	280
63	64	65	66	67	281
63	64	65	66	67	282
63	64	65	66	67	283
63	64	65	66	67	284
63	64	65	66	67	285
63	64	65	66	67	286
63	64	65	66	67	287
63	64	65	66	67	288
63	64	65	66	67	289
63	64	65	66	67	290
63	64	65	66	67	291
63	64	65	66	67	292
63	64	65	66	67	293
63					

08/013543

08/013543

FIG. 15




08/013543

11/383079


FIG. 16A

11/383079
DRAFTMAN
CLASS SUBCLASS
O.G. FIG.




07/383073
08/013543

FIG. 16B



1/383073
08/013543


FIG. 17A



08/013543

17/388079


FIG. 17B



68/613543

17/388079

FIG. 17C



08/013543

FIG. 17D





FIG. 17D
DRAFTMAN
SUBCLASS

1974-01-22

08/013543

11/388079

FIG. 17E



08/013543

17/388079

FIG. 17F






FIG. 18



88/013543

17/383073

FIG. 19A



08/01/5543

~~67/388079~~

FIG. 19B

FIG. 19B
SEARCH "PRESIDENT" OR "DIRECTOR"
ON LINE m
SEARCH "DEPARTMENT" OR "SECTION"
ON LINE m
SET LINE m IN 57 & c←1
SET LINE m IN 56 & b←b+1
B
D
A
B
D





FIG. 19C

08/013543

17-388079



FIG. 19C
D.G. FIG.
CLASS SUBCLASS
TRACTION



08/03543

17-88073


FIG. 19D



08/01/3543

11/388079

FIG. 20



08/01/3543

~~11/388079~~

FIG. 21

SEARCHED	INDEXED	FILED
CLASS	CLASS	SUBCLASS
DRAFTSMAN		

75

76

KEY WORD
XX

75

76

KEY WORD
XX


XX CORPORATION	03(123) 4567
XX CORPORATION	03(123) 4568
△△BRANCH	
XO CORPORATION	03(123) 4569
X△ CORPORATION	03(123) 4570

XX CORPORATION	03(123) 4567
XX CORPORATION	03(123) 4568
△△BRANCH	
CORPORATION	XX SERVICE
	03(123) 1234

08/013543


11/383079

FIG. 22



SEARCHED
INDEXED
O.G. FIG.
CLASS 367
SUBCLASS 1
DRAFTSMAN


FIG. 24



08/013543

11/388073


FIG. 23



08/013545

~~07/388079~~


FIG. 25A



08/03/543

11/388073


FIG. 25B



68/013543

~~68/388073~~

FIG. 25C



SEARCHED INDEXED
SERIALIZED FILED
JUL 1 1971
GRAFTMAN

08/013543

~~11/388075~~

FIG. 26A

FIG. 26B




FIG. 27A






FIG. 27B




08/013543

~~11/388079~~



Expedited


FIG. 28



08/03543

~~07/388079~~


FIG. 29



08/013543

~~07/388079~~


FIG. 30A



08/013543

11/388079


FIG. 30B



08/03543

~~11/388079~~

FIG. 31A



68/013543

11/388079

FIG. 31B





FIG. 32



COMBINED DECLARATION AND POWER OF ATTORNEY
FOR PATENT APPLICATION

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name;
I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled INFORMATION PROCESSING

APPARATUS

, the specification of which

is attached hereto. was filed on _____ as Application Serial No. _____

and was amended _____ (if applicable).

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose information which is material to the examination of this application in accordance with Title 37, Code of Federal Regulations, §1.56(a).

I hereby claim foreign priority benefits under Title 35, United States Code, §119 of any foreign application(s) for patent or inventor's certificate listed below and have also identified below any foreign application for patent or inventor's certificate having a filing date before that of the application on which priority is claimed:

Country	Application No.	Filed (Day/Mo./Yr.)	Priority Claimed (Yes/No)
JAPAN	63-193299	2 August, 1988	YES
JAPAN	63-223626	8 September, 1988	YES
JAPAN	63-312926	13 December, 1988	YES

I hereby appoint Joseph M. Fitzpatrick (Registration No. 17,398), John Thomas Cella (Registration No. 17,356), Lawrence F. Scinto (Registration No. 18,973), William J. Brunet (Registration No. 20,452), Robert L. Baechtold (Registration No. 20,860), John A. O'Brien (Registration No. 24,367), Nels T. Lippert (Registration No. 25,888), John A. Krause (Registration No. 24,613), Henry J. Renik (Registration No. 25,499), Peter Saxon (Registration No. 24,947), Anthony M. Zupcic (Registration No. 27,276), Charles P. Baker (Registration No. 26,702), Stevan J. Bosses (Registration No. 22,291), Edward E. Vassallo (Registration No. 29,117), Ronald A. Clayton (Registration No. 26,718), Sidney R. Bresnick (Registration No. 24,094), Frederick J. Dorchak (Registration No. 29,298), Lawrence A. Stahl (Registration No. 30,110), Laura A. Bauer (Registration No. 29,767), Gary R. Molnar (Registration No. 30,299), Leonard P. Diana (Registration No. 29,296), David M. Quinlan (Registration No. 26,641), Nicholas N. Kallas (Registration No. 31,530), William M. Wannisky (Registration No. 28,373), Lawrence Alaburda (Registration No. 31,583), Frank J. Kowalski (Registration No. 28,434), Lawrence S. Perry (Registration No. 31,865), Robert H. Fischer (Registration No. 30,051), Christopher Philip Wrist (Registration No. 32,078), Gary M. Jacobs (Registration No. 28,861), Grover F. Fuller, Jr. (Registration No. 31,760), Rudolph J. Anderson, Jr. (Registration No. 16,792), and Michael K. O'Neill (Registration No. 32,622).

30
my attorneys to prosecute this application and to transact all business in the Patent and Trademark Office connected therewith.

Address all correspondence to:

Fitzpatrick, Cella, Harper & Scinto
277 Park Avenue
New York, N.Y. 10172
Telephone No. (212) 758-2400

6297

**COMBINED DECLARATION AND POWER OF ATTORNEY
FOR PATENT APPLICATION**

(Page 2)

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Full Name of Sole or First Inventor RYOICHIRO SATO

Inventor's signature Ryoichiro Sato

Date July 27, 1989 Citizen/Subject of JAPAN

Residence 10-3-315, Tsurumichuo/2-chome, Tsurumi-ku,

Post Office Address Yokohama-shi, Kanagawa-ken, Japan

c/o Canon Kabushiki Kaisha
30-2, 3-chome, Shimomaruko, Ohta-ku, Tokyo, Japan

Full Name of Second Joint Inventor, if any YOJI FURUYA

Second Inventor's signature Yoji Furuya

Date July 27, 1989 Citizen/Subject of JAPAN

Residence 2-207, Ribere Koyodai, 5-10, Koyodai,

Post Office Address Inagi-shi, Tokyo, Japan

c/o Canon Kabushiki Kaisha
30-2, 3-chome, Shimomaruko, Ohta-ku, Tokyo, Japan

Full Name of Third Joint Inventor, if any _____

Third Inventor's signature _____

Date _____ Citizen/Subject of _____

Residence _____

Post Office Address _____

Full Name of Fourth Joint Inventor, if any _____

Fourth Inventor's signature _____

Date _____ Citizen/Subject of _____

Residence _____

Post Office Address _____

Full Name of Fifth Joint Inventor, if any _____

Fifth Inventor's signature _____

Date _____ Citizen/Subject of _____

Residence _____

Post Office Address _____

Full Name of Sixth Joint Inventor, if any _____

Sixth Inventor's signature _____

Date _____ Citizen/Subject of _____

Residence _____

Post Office Address _____